16S DIY Battery Kit

AE-E-BUILD-16S



Build a low-voltage LiFePO4 storage system with a clearly defined package: case kit without cells, or a kit with matched cells for professional assembly. Final component list and electrical limits are agreed per quotation.

Design illustration; final component list and specifications are agreed for the selected configuration.

TECHNICAL INFORMATION

Proposed configuration

Supply format	Case kit: no cells. Cell-kit option: 16 compatible cells, assembly required.
Cell arrangement	16S1P
Proposed nominal voltage	51.2 V (16 × 3.2 V)
Cell-kit / assembled option	314 Ah
Calculated nominal energy with 314Ah cells	16.0768 kWh (51.2 V × 314 Ah)
BMS selection	16S LiFePO4; current rating and firmware by final BOM
Continuous charge / discharge	Confirm for the quoted configuration
Protection rating / location	IP rating unverified; plan a dry indoor installation
Cycle life / warranty	Confirm for the quoted configuration
System role	DC battery storage; external inverter required for AC loads
Case-kit energy	No stored energy without cells

16S DIY 电池套件

AE-E-BUILD-16S



面向低压磷酸铁锂储能系统，区分不含电芯的箱体套件与含配套电芯的组装套件。具体物料清单、电芯尺寸与电气限制按报价确认，由具备相应能力的人员组装。

外观为设计示意，具体物料与参数按所选配置确认。

技术信息

规划配置

交付形式	箱体套件不含电芯；含芯套件选项配 16 只适配电芯，需组装。
电芯连接	16S1P
规划标称电压	51.2 V (16 × 3.2 V)
含芯套件 / 成品配置	314 Ah
314Ah 电芯配置的计算标称电量	16.0768 kWh (51.2 V × 314 Ah)
BMS 选配	16S 磷酸铁锂，电流等级及固件按最终物料清单确认
持续充放电电流	按报价配置确认
防护等级 / 放置环境	IP 等级尚未核实，按干燥室内环境规划
循环寿命 / 质保	按报价配置确认
系统功能	直流电池储能，交流负载需外置逆变器
空箱套件电量	未装电芯时不具有储能容量