Pre-assembled 16kWh Battery

AE-E-READY-16



A proposed factory-assembled LiFePO4 battery for residential solar storage and backup through a matched external inverter. Cells are fitted within the enclosure; commissioning, inverter settings and installation remain project-specific.

Design illustration; final component list and specifications are agreed for the selected configuration.

TECHNICAL INFORMATION

Proposed configuration

Supply format	Cells installed in enclosure; no inverter included; commissioning required.
Cell arrangement	16S1P
Proposed nominal voltage	51.2 V (16 × 3.2 V)
Cell-kit / assembled option	314 Ah
Calculated nominal energy with 314Ah cells	16.0768 kWh (51.2 V × 314 Ah)
BMS selection	16S LiFePO4; current rating and firmware by final BOM
Continuous charge / discharge	Confirm for the quoted configuration
Protection rating / location	IP rating unverified; plan a dry indoor installation
Cycle life / warranty	Confirm for the quoted configuration
System role	DC battery storage; external inverter required for AC loads

16kWh 预组装箱式电池

AE-E-READY-16



面向住宅光伏配储与备电的预组装磷酸铁锂箱式电池规划配置，电芯在箱内完成组装，需搭配适配的外置逆变器；安装、调试与逆变器设置按项目确认。

外观为设计示意，具体物料与参数按所选配置确认。

技术信息

规划配置

交付形式	箱内已装电芯，不含逆变器，仍需安装与调试。
电芯连接	16S1P
规划标称电压	51.2 V (16 × 3.2 V)
含芯套件 / 成品配置	314 Ah
314Ah 电芯配置的计算标称电量	16.0768 kWh (51.2 V × 314 Ah)
BMS 选配	16S 磷酸铁锂，电流等级及固件按最终物料清单确认
持续充放电电流	按报价配置确认
防护等级 / 放置环境	IP 等级尚未核实，按干燥室内环境规划
循环寿命 / 质保	按报价配置确认
系统功能	直流电池储能，交流负载需外置逆变器